



# IDEAL CABLING

## PROPOSAL FOR SERVICES

Town of Wrightstown

Wrightstown, WI

April 22, 2022

### Overview

Ideal Cabling is pleased to submit this proposal for services to support The Town of Wrightstown in its needs to expand fiber optic internet to its residents. The overall project would expand Ideal Communications existing fiber optic network an estimated 7.92 miles allowing Ideal Communications to provide fiber optic internet service to an estimated 129 additional properties. This project is estimated to take 12-14 months to complete from the date of the phase 1 payment issuance. Ideal Communications currently services an estimated 46 properties in the Town of Wrightstown. Total project price of \$248,000.

### Scope of Work

- Phase 1 – Map 1 (Estimated Length of 3.11 Miles – Servicing an estimated 63 properties)
  - Expand Ideal Communications fiber optic network from Ridge Royale to cover Ledetop Dr. from Day St. to School Rd. This expansion also includes the following roads Ledge-top Court, Fawn Court, Deer Haven Court and Deer Haven Road.
  - Provide and install 1.25 inch HDPE conduit along the path shown in “Phase 1 – Map 1 Town of Wrightstown Proposed Infrastructure”.
  - Provide and install fiber optic hand holes along the path shown in “Phase 1 – Map 1 Town of Wrightstown Proposed Infrastructure”.
  - Provide and install main line fiber optic cable inside of HDPE hand holes along the path shown in “Phase 1 – Map 1 Town of Wrightstown Proposed Infrastructure”.
  - Provide and install fiber optic network splitters in hand holes to allow for resident connections to be made along the path shown in “Phase 1 – Map 1 Town of Wrightstown Proposed Infrastructure”.
- Phase 2 – Map 1 (Estimated Length of .95 Miles – Servicing an estimated 25 properties)
  - Expand Ideal Communications fiber optic network from Elmro Rd. Subdivision to cover an estimated .35 miles of Fair Rd. from Elmro Rd. to Oak Ridge Rd. This expansion also includes the following road Vande Voort Court.
  - Provide and install 1.25 inch HDPE conduit along the path shown in “Phase 2 – Map 1 Town of Wrightstown Proposed Infrastructure”.
  - Provide and install fiber optic hand holes along the path shown in “Phase 2 – Map 1 Town of Wrightstown Proposed Infrastructure”.
  - Provide and install main line fiber optic cable inside of HDPE hand holes along the path shown in “Phase 2 – Map 1 Town of Wrightstown Proposed Infrastructure”.

- Provide and install fiber optic network splitters in hand holes to allow for resident connections to be made along the path shown in “Phase 2 – Map 1 Town of Wrightstown Proposed Infrastructure”.
- Phase 2 – Map 2 (Estimated Length of 3.86 Miles – Servicing an estimated 41 properties)
  - Expand Ideal Communications fiber optic network from Elmro Rd. Subdivision to cover an estimated 2.02 Miles miles of Elmro Rd. from Fair Rd. to Partridge Rd. This expansion also includes the following roads estimated .51 miles of Meadowlark Road, Eagle Landing Court, estimated .55 Miles Partridge Road and Legacy Lane.
  - Provide and install 1.25 inch HDPE conduit along the path shown in “Phase 2 – Map 2 Town of Wrightstown Proposed Infrastructure”.
  - Provide and install fiber optic hand holes along the path shown in “Phase 2 – Map 2 Town of Wrightstown Proposed Infrastructure”.
  - Provide and install main line fiber optic cable inside of HDPE hand holes along the path shown in “Phase 2 – Map 2 Town of Wrightstown Proposed Infrastructure”.
  - Provide and install fiber optic network splitters in hand holes to allow for resident connections to be made along the path shown in “Phase 2 – Map 2 Town of Wrightstown Proposed Infrastructure”.

## Out of Scope Work

- Electronics
- Resident private dwelling installation and service
- Commercial private dwelling installation and service
- Expansion of fiber optic network beyond the Proposed Infrastructure Maps Dated April 2022

## PAYMENT TERMS

Ideal Cabling proposes a payment of \$124,000 be made to procure products i.e. HDPE conduit, handholes, fiber optic cable, fiber optic splitters, finalize construction coordination and start Phase 1 construction as shown on Phase 1 – Map 1 Town of Wrightstown Proposed Infrastructure Map.

Once Phase 1 construction has been completed a payment of \$99,200 to be made to start construction on Phase 2 construction as shown on Phase 2 – Map 1 Town of Wrightstown Proposed Infrastructure Map and Phase 2 – Map 2 Town of Wrightstown Proposed Infrastructure Map.

Upon completion of Phase 2 construction the remaining balance of \$24,800 will be paid.

If you have questions on this proposal, feel free to contact Josh at your convenience by email at [jdavies@idealcablewi.com](mailto:jdavies@idealcablewi.com) or by phone at (920) 415-3479. We will be in touch with you to arrange a follow-up conversation on the proposal. Thank you for your consideration.

## AGREEMENT

By signing this contract, The Town of Wrightstown, allows Ideal Cabling to complete the work agreed upon above. Proposal valid for 60 days from summital date.

Any materials, hardware, or labor not paid for will be subject to legal and fiscal action taken against client signee list below.

All hardware installed remains property of Ideal Cabling until all invoices have been satisfied. Should buyer not remit payment all hardware installed by Ideal Cabling will be repossessed after a final 7-day notice has been issued. By signing this contract, you agree to allow Ideal Cabling' employees on to signee property for repossession purposes should all accounts payable not be satisfied.

By signing this contract, the signee allows Ideal Cabling' staff on the signee's property to complete work stated above and releases Ideal Cabling from all on-site liabilities.

---

Print Name

---

Client Signature

---

Date

---

Ideal Cabling Rep Print Name

---

Ideal Cabling Rep Signature

---

Date